

Infrastructure Solutions Catalog



About Vertiv	3
Prefabricated Modular Data Centers	4
Vertiv™ SmartMod™	
Vertiv™ SmartMod™ Max	
Vertiv™ Modular Designer Lite	
Vertiv™ SmartMod™ Combo	
Vertiv™ MegaMod™	
Vertiv™ SmartMod™ HDX	
Vertiv™ Custom	

Hybrid Data Center Design	
Vertiv™ Power Modules & Skid	
Vertiv™ Unit IT	
Vertiv™ Cooling Skids	

When Innovation meets Sustainabilty	38
Vertiv™ TimberMod™	38



## Vertiv

Nearly all aspects of our lives involve the use of technology. It is how we work and play and do anything in between. This connectivity or use of data is built into the very fabric of our society. It is vital to human progress. Vertiv believes there is a better way to meet this accelerating demand for data — one driven by passion and innovation.

As industry experts, we collaborate with our customers to envision and build future-ready infrastructures. We leverage our portfolio of hardware, software, analytics, and services, to ensure our customers' vital applications run continuously, perform optimally, and scale with business needs.

#### Unlocking Efficiency and Agility with Prefabricated Solutions

Over the past decade, a notable shift has occurred in data center construction methods. In the past, traditional "brick and mortar" approaches involved piecing together system components and constructing the building, followed by equipment installation and commissioning. However, in contrast, modern modular data centers are conceived, produced, and tested off-site concurrently with site preparation, yielding over 40% time savings compared to conventional builds. Prefabricated modules prioritize seamless integration, curtailing onsite labor demands and logistical intricacies.

This transition offers rapid and efficient design, augmented risk management, and cost predictability through factory integration. Modular data centers assure scalability for future expansions, embody repeatable designs, and exhibit superior quality via factory control. This simplified assembly enables swift transportation by road, rail, or sea, contributing to enhanced deployment agility.

#### **Our Brands**

Vertiv<sup>™</sup> SmartMod<sup>™</sup> | Vertiv<sup>™</sup> Power Module | Vertiv<sup>™</sup> TimberMod<sup>™</sup>

Vertiv<sup>™</sup> MegaMod<sup>™</sup> | Vertiv<sup>™</sup> HydroMod<sup>™</sup>

#### **Our Production Facilities**

#### **Headquarters:**

- Oreškovićeva 6n/2, Zagreb, 10 000, Croatia
- 505 N Cleveland Ave, Westerville, 43082, USA

#### **Production facilities:**

Rugvica, Croatia 1 Ras Al Khaimah, UAE Anderson, South Carolina Tijuana, Mexico

Donegal, Ireland

Τ

Columbus. Ohio

Т



Here you can learn more about

VERTIV INFRASTRUCTURE SOLUTIONS

### **Key Benefits**

#### Rapidly Deploy. Standardize. Repeat

Speed data center builds with pre-integration, prefabrication, and flexible designs when you can't wait

#### **Reduce Risks**

• Control budget, improve safety, and mitigate risk for stakeholders without compromising quality

#### **Energy Efficient Design**

• Lower site PUE and reduce environmental impact while controlling costs

#### Zero Floor Space Waste

Recover precious white space and scale as you grow

# Prefabricated Modular Data Centers

## Benefits of using a Prefabricated modular data center

Prefabricated modular data centers offer a host of compelling advantages that are transforming the landscape of data center design and deployment. Their inherent modularity ensures scalability, allowing organizations to easily expand their infrastructure as demand grows. The standardized nature of these modules streamlines maintenance and operation, promoting efficiency and reducing costs. Additionally, the sustainability aspect cannot be overlooked, as the use of recyclable materials, like steel, in the manufacturing process reduces environmental impact. By integrating assembly within controlled factory environments, these data centers not only save time but also minimize onsite disruptions, resulting in faster deployment and optimized performance. Overall, prefabricated modular data centers stand as a testament to innovation, offering adaptable, cost-effective, and environmentally responsible solutions for the everevolving demands of the digital age.





## <sup>0 - 100 kW</sup> Vertiv<sup>™</sup> SmartMod<sup>™</sup>

Prefabricated Modular Data Centers up to 100kW normally fall under all-in-one modular data centers, where all the equipment necessary for normal data center functionality is placed within a single transportable module. Vertiv can support this range with its Vertiv<sup>™</sup> SmartMod<sup>™</sup> that is a perfect fit for IT deployments between 2 and 14 racks or 100 kW or less.

#### SmartMod<sup>™</sup> Features

- Modular and scalable Vertiv<sup>™</sup> Liebert<sup>®</sup> UPS power protection
- Close-coupled in-row Vertiv<sup>™</sup> Liebert<sup>®</sup> CRD thermal management units with intelligent Vertiv<sup>™</sup> iCOM<sup>™</sup> Edge controls
- Classic and cost-effective
   Vertiv<sup>™</sup> racks
- Vertiv rack PDUs
- Thermal containment to isolate hot aisle and cold aisle airflows for optimum thermal performance
- Automatic Transfer Switch (ATS) to reliably select normal or emergency power sources
- Overhead infrastructure, including piping, electrical distribution, and fiber ducts
- Clean agent fire suppression and aspiration smoke detection (as optional item)
- Vertiv<sup>™</sup> Environet<sup>™</sup> Alert real-time monitoring and visualization for critical infrastructure (as optional item)

SmartMod offers a simple way to install capacity in a fraction of the time, providing at the same time enhanced levels of availability, efficiency, and control in self-contained enclosures that can be deployed securely, virtually anywhere.



Enclosure Cut-Out view of Vertiv™ SmartMod™

SmartMod is not a one size fits all system. It is designed to be configurable to right-size to your rack footprint, IT load, desired redundancy, location, and other additional options so you can achieve the optimal solution based on a specific need. All subsystems are factory installed into a secure, weatherproof and transportable enclosure – simplifying and drastically shortening the on-site time required to install and startup, and reducing the potential for risk, quality, or schedule delays.



Top view of SmartMod

#### Vertiv<sup>™</sup> SmartMod<sup>™</sup> Specifications

Standard Design Specifications	Sm	artMod	
Enclosure External Dimensions			
Enclosure Length (mm)	6426, 8010, 9	594, 11178 or 11970	
Enclosure Width (mm)	:	3400	
Enclosure Height (mm)		3260	
Module Overall Length <sup>(1)</sup>	6426-12045 mm (@ 6426 mm) 8010-13630 mm (@ 8010 mm) 9594-15215 mm (@ 9594 mm) 11178-16795 mm (@ 11178 mm) 11970-17590 mm (@ 11970 mm)		
Lifting Weight <sup>(2)</sup>	Up to 1800	0 kg per module	
Input AC Parameters			
Region	EMEA	NAM	
Voltage/Frequency	400 VAC, 50 Hz	Input: 480 or 208V 60Hz, Rack: 208/120V 60 Hz	
IT Racks			
Rack Height	42U (2000 mm) 47U (2200 mm) 48U (2265 mm)	42U (2000 mm) 47U (2200 mm) 48U (2265 mm)	
Rack Depth	1100 mm	1100 mm	
Rack Width	600 mm and/or 800 mm	600 mm and/or 800 mm	
Rack Load	8 kN	8 kN	
Electrical			
Electrical Distribution Board	1 or 2	1 or 2	
Automatic Transfer Switch	1 or 2	1 or 2	
UPS Model	APM150	EXM20 - EXM200	
UPS Cabinet	1 or 2	1 or 2	
UPS Module Redundancy	N or N+1	N or N+1	
UPS Rating	Up to 150 kVA (@APM150)	Up to 200 kVA (@EXM200)	
Battery Backup Time <sup>(3)</sup>	Up to 13 min @ 100 kW Up to 30 min @ 50 kW	Up to 5 min @ 100 kW Up to 10 min @ 50 kW	
Busbar System	2 per row	2 per row	
Rack Load	Up to 17 kW	Up to 17 kW	
PDU	2 per rack	2 per rack	
PDU Capacity (max)	3x32 A @ 230/400 V-3ph	2x60 A @ 120/208 V-3ph	
PDU Type	Basic, Monitored (unit level) or     Basic, Monitored (unit level) or       Switched (unit level)     Switched (unit level)		
Mechanical (HVAC)			
Air Conditioning Type	In-row, direct expansion	In-row, direct expansion	
Air Conditioning Redundancy	N or N+1	N or N+1	
Air Conditioning Units	up to 6x CRD25 with up to 6x CCD25 externally mounted condensers	up to 8x CRV019 with 8x MCL040 Condensers up to 5x CR035 with 5x MCL055 Condensers	
Cooling Capacity for IT Load (35°C)	up to 100 kW	up to 100 kW	
Exterior Ambient Operating Range	-30°C to +52°C	-22°F to 125°F	

<sup>(1)</sup> Length presented is the maximum transport length. It includes an enclosure with attached condenser units.

<sup>(2)</sup> Weight presented is the estimated weight of shipping/lifting the unit with empty IT racks and empty UPS battery cabinets.

(3) Battery backup time at beginning of life (BOL). Maximum available backup time may vary based on solution input parameters (presented here 2 options for different IT Load requirements).



## Vertiv<sup>™</sup> SmartMod<sup>™</sup> 30 kW

#### CASE STUDY



#### 30 kW

IT Load

#### **Customer Need**

- Two smaller, portable data centers to support airport operations
- Special color and coating due to site conditions
- Strict delivery schedule

### Solution

- Standard Vertiv™ SmartMod™
- IT rack quantity: 8 (800mm x 1100mm x 42U)
- 2N UPS electrical topology with ATS
- N+1 redundancy on UPS and cooling
- 10 min battery back up time
- Fire detection& suppression, VESDA
- Intrusion detection

- Customer impressed with speed of response and speed of delivery
- Vertiv technical know-how employed to delivery turn-key data center infrastructure

## Vertiv<sup>™</sup> SmartMod<sup>™</sup> 34 kW

### CASE STUDY



### 34 kW

IT Load

#### **Customer Need**

- DX as Thermal Solution, 10 kW/Rack
- N+1 Electrical redundancy, N+1 Cooling redundancy, and Entrance Vestibule
- Special color and coating due to site conditions

### Solution

- Standard Vertiv™ SmartMod™
- IT rack quantity: 10, 3-4 kW per rack density
- N+1 redundancy on UPS and cooling
- Cooling through an In-Row cooling system with our CRV units (019/020)

- Reclaimed space
- Better capital planning
- Quick delivery



## Vertiv<sup>™</sup> SmartMod<sup>™</sup> 70 kW

### CASE STUDY



### 70 kW

IT Load

### **Customer Need**

• Smaller data center that can be deployed quickly

### Solution

- Standard Vertiv™ SmartMod™
- IT rack quantity: 4 (800 mm x 1100 mm x 42U) & 4 (600 mm x 1100 mm x 42U)
- 2N UPS electrical topology with ATS
- N+1 redundancy on cooling
- 10 min battery back up time
- Fire detection& suppression, VESDA
- Intrusion detection

- Early engagement with the customer helped drive solution according to their needs
- Fast time to respond solution from the configurator

## 100 - 200 kW Vertiv<sup>™</sup> SmartMod<sup>™</sup> Max

Vertiv<sup>™</sup> SmartMod<sup>™</sup> Max is a simple, configurable system that extends the capability of the SmartMod<sup>™</sup> platform to larger deployments. For IT deployments up to 210 kW and up to 26 IT racks, SmartMod<sup>™</sup> Max offers a simple way to install capacity in a fraction of the time a typical IT build might take.

Based on preffered cooling option, SmartMod Max is available in two versions:

- SmartMod Max DX featuring direct expansion based cooling units
- SmartMod Max CW featuring chilled water based thermal management units

#### SmartMod<sup>™</sup> Max incorporates:

- Vertiv<sup>™</sup> Liebert<sup>®</sup> UPS power protection options based on your needs - using either the modular and scalable Vertiv<sup>™</sup> Liebert<sup>®</sup> APM / Vertiv<sup>™</sup> Liebert<sup>®</sup> APM Plus, or the space-saving Vertiv<sup>™</sup> Liebert<sup>®</sup> EXM2
- In-row Liebert<sup>®</sup> thermal management units with intelligent controls
- Classic and cost-effective
   Vertiv racks
- Vertiv™ rack PDUs
- Thermal containment to isolate hot aisle and cold aisle airflows for optimum thermal performance
- Automatic Transfer Switch (ATS) to reliably select normal or emergency power sources
- Overhead infrastructure, including piping, electrical distribution, and fiber ducts
- Clean agent fire suppression and aspiration smoke detection (as optional items)
- Vertiv<sup>™</sup> Critical Insight real-time monitoring and visualization for critical infrastructure (as optional item)

Again, all subsystems are factory installed into a secure, weatherproof and transportable enclosure – simplifying and drastically shortening the on-site time required to install and startup, and reducing the potential for risk, quality, or schedule delays.

#### Components overview of Vertiv™ SmartMod<sup>™</sup> Max DX



Enclosure Cut-Out view of Vertiv™ SmartMod™ Max DX

#### Components overview of Vertiv<sup>™</sup> SmartMod<sup>™</sup> Max CW





### Vertiv<sup>™</sup> SmartMod<sup>™</sup> Max Specifications EMEA

Standard Design Specifications	SmartMod™ Max DX	SmartMod™ Max CW			
Enclosure Length					
Enclosure Length (mm)	8010, 959	8010, 9594, 11178 or 11970			
Single Module Width (mm) <sup>(1)</sup>		2900			
Enclosure Width (mm)		5810			
Enclosure Height (mm)		3333			
Module Overall Length (mm) <sup>(2)</sup>	8010 - 13670 (@ 8010) 9594 - 15254 (@ 9594) 11178 - 16838 (@ 11178) 11970 - 17630 (@ 11970)	8830 (@ 8010) 10415 (@ 9594) 12100 (@ 11178) 12790 (@ 11970)			
Chiller Skid Dimensions (WxL) (mm)	-	3440 x 6865			
Lifting Weight <sup>(3)</sup>	Up to 17000 kg per module	Up to 17000 kg per module Up to 8000 kg per chiller skid <sup>(4)</sup>			
Input AC Parameters					
Region		EMEA			
Voltage/Frequency	400 \	VAC, 50 Hz			
IT Racks					
Rack Height	42U (2000 mm) 47U (2200 mm) 48U (2265 mm)	42U (2000 mm)			
Rack Depth	11	1100 mm			
Rack Width	600 mm :	600 mm and/or 800 mm			
Rack Load	8 kN				
Electrical					
Electrical Distribution Board		2			
Automatic Transfer Switch		1 or 2			
UPS Model	APM150, A	PM Plus or EXM2			
UPS Cabinet		2			
UPS Module Redundancy	N/N+1 for A	PM or N for EXM2			
UPS Rating	Up to 150kVA (@ APM150) (	or 250kVA (@ APM Plus or EXM2)			
Battery Backup Time	1-10 min	1-15 min			
Busbar System	Two	o per row			
Rack Load	Up	Up to 17 kW			
PDU	Two	o per rack			
PDU Capacity (max)	3x32 A @ 3	3x32 A @ 230/400 V - 3ph			
PDU Type	Basic, Monitored (unit level) or Switched (unit level)				
Mechanical (HVAC)					
Air Conditioning Type	In-Row, Direct Expansion	In-Row, Chilled Water			
Air Conditioning Redundancy		N+1			
Air Conditioning Units	Up to 12x CRD25	Up to 8x CRC60			
Cooling Capacity for IT Load (35°C)	Up to 200 kW Up to 210 kW				
Exterior Ambient Operating Range	-30°C to +52°C				

 $^{(1)}\operatorname{SmartMod}^{{\scriptscriptstyle\mathsf{TM}}}$  Max enclosure consists of two (2) modules.

<sup>C0</sup> Length presented is the maximum transport length. For SmartMod Max DX it includes an enclosure with attached condenser units. For SmartMod Max CW it includes the piping extension attached to enclosure, while chiller skid is transported separately.

<sup>(3)</sup> Weight presented is the estimated weight of shipping/lifting the unit with empty IT racks and empty UPS battery cabinets.

(4) The lifting weight of chiller skid includes 3 chillers, 6 tanks and piping (water or glycol excluded).

#### Vertiv<sup>™</sup> SmartMod<sup>™</sup> Max Specifications NAM

Standard Design Specifications	SmartMod™ Max DX	SmartMod™ Max CW	
Enclosure Length			
Enclosure Length (mm)	9754, 1128, 12192, 1280	2, 14326, 15850	
Single Module Width <sup>(1)</sup>	9' 6" (2900 mm)		
Enclosure Width	19' (5810 m		
Enclosure Height (mm)	3402		
	32' (9754 m	ım)	
	37' (11278 n	nm)	
Module Overall Length <sup>(2)</sup>	40' (12192 n	nm)	
	42' (12802 r		
	47' (14326 r 52' (15850 r		
Chiller Skid Dimensions (WxL)	Chiller Selection E		
Lifting Weight <sup>(3)</sup>	Project Deper	•	
Input AC Parameters		nuent	
-	NAM		
Region			
Voltage/Frequency	400 VAC, 50	5 H2	
IT Racks			
Rack Height	42U (2000 mm) 47U (2200 mm) 48U (2265 mm)	42U - 78" (2000 mm)	
Rack Depth	43" (1100 m	nm)	
Rack Width	23" (600 mm) / 31" (800 mm)		
Rack Load	8 kN		
Electrical			
Electrical Distribution Board	2		
Automatic Transfer Switch	1 or 2		
UPS Model	EXM		
UPS Cabinet	2		
UPS Module Redundancy	N, N+1, 2N		
UPS Rating	100, 150, 200	D kW	
Battery Backup Time	5 min		
Busbar System	Two per ro	wc	
Rack Load	Up to 17 k	W	
PDU	Two per ra	ack	
PDU Capacity (max)	30A / 60A @ 120 / 208 V		
PDU Type	Basic / Monitored (unit level) / Switched (unit level)		
Mechanical (HVAC)			
Air Conditioning Type	In-Row, Direct Expansion	In-Row, Chilled Water	
Air Conditioning Redundancy	N+1		
Air Conditioning Units	Up to 8x CRV019 with 8x Condensers per row Up to 5x CR035 with 5x MCL055 Condensers per row	Based on IT load (2-8 CRC60) tied to piping space	
Cooling Capacity for IT Load (35°C)	Up to 200	kW	
Exterior Ambient Operating Range	-30°C to +5	D°0	

 $^{\mbox{(1)}}$  SmartMod Max enclosure consists of two (2) modules.

(2) Length presented is the maximum transport length. For SmartMod Max DX it includes an enclosure with attached condenser units. For SmartMod Max CW it includes the piping extension attached to enclosure, while chiller skid is transported separately.

(3) Weight presented is the estimated weight of shipping/lifting the unit with empty IT racks and empty UPS battery cabinets.



## Vertiv<sup>™</sup> SmartMod<sup>™</sup> Max 36 kW

#### CASE STUDY



#### 36 kW

IT Load

#### **Customer Need**

- Telecommunications support in deserted area with limited infrastructure
- DC Rack power with N+1 UPS backup
- 20 racks & 36 kW of Total IT load
- Preparation for future increase in IT load

### Solution

- Dual Module Data Center solution
- 20 DC powered racks installed
- 48 VDC Powered by Netsure 7100 with 63 kW UPS capacity
- VRLA Battery Technology
- N+1 wall mounted air cooling up to 84 kW
- Vesda Fire detection with NOVEC1230 fire extinguishing system

- Standard product solution
- Successful and clean dual module deployment
- Exceeding customer expectations of quality

## Vertiv<sup>™</sup> SmartMod<sup>™</sup> Max 90 kW

#### CASE STUDY



#### 90 kW

IT Load

#### **Customer Need**

- 24 racks, up to 100 kW, TIER III availability level
- Quick delivery time

#### Solution

- Off-the-shelf Vertiv<sup>™</sup> SmartMod<sup>™</sup> Max product 24 racks, 90 kW IT with country-specific modifications (60 Hz power supply, SASO-certified cooling solution)
- 2N power supply topology with Vertiv™ Liebert® APM row-based UPS and built-in batteries
- N+1 cooling per rack row with Vertiv<sup>™</sup> Liebert<sup>®</sup> CR019 units (airfreighted from the US)
- VESDA fire detection and NOVEC1230 fire extinguishing system
- CCTV and access control integrated in the factory
- Externally-mounted condensers sized for +52°C ambient

- Standard product exceeding customer expectations
- 14 weeks EXW availability
- KSA Partner responsible for on-site turnkey works
- Future expansion projects already in the pipeline



## Vertiv<sup>™</sup> SmartMod<sup>™</sup> Max 150 kW

#### CASE STUDY



#### 150 kW

IT Load

#### **Customer Need**

• 150 kW IT Load, 2N power, N+1 cooling, additional office space to the Data Center area

#### Solution

- Vertiv™ SmartMod™ Max DX including:
  - Dual module enclosure, 11970 mm x 5810 mm x 3330 mm (LxWxH)
  - Cooling: 10x Liebert<sup>®</sup> CR025 (n+1 redundancy per row) + 10 Liebert HCR33 condensers
  - UPS: Vertiv™ Liebert® APM 150kVA
  - Racks: 24x Knürr™ Miracel2 server racks
  - PDUs: 2 per rack, Vertiv™ Geist™, metered
  - Fire suppression system: NOVEC

- Standard configuration allowing quick delivery (20 weeks EXW)
- Factory construction quality allowing quick deployment and commissioning
- Office space based on SmartMod-type module

## Vertiv<sup>™</sup> Modular Designer Lite

Vertiv<sup>™</sup> Modular Designer Lite is a web-based solution tailored for configuring Vertiv<sup>™</sup> SmartMod<sup>™</sup> and Vertiv<sup>™</sup> SmartMod<sup>™</sup> Max all-in-one modular data centers.





16

Here you can learn more about

► VERTIV MODULAR DESIGNER LITE

## 200 - 600 kW Vertiv<sup>™</sup> SmartMod<sup>™</sup> Combo

Standardized prefabricated data center offerings for IT deployments from 200 kW to 600 kW and up to 104 IT racks in total can be addressed with the Vertiv<sup>™</sup> SmartMod<sup>™</sup> Combo. The modules are shipped in prefabricated sections, then connected and sealed at your site by experienced Vertiv personnel to create a fully functional data center with dedicated White Space and external Vertiv<sup>™</sup> Power Module. SmartMod Combo leverages core Vertiv<sup>™</sup> Critical Power, Thermal Management, and Monitoring & Control Technologies.

#### SmartMod<sup>™</sup> Combo incorporates:

#### Vertiv<sup>™</sup> Power Module unit:

- Monolithic Vertiv<sup>™</sup> Liebert<sup>®</sup> EXL S1 UPS with leading power per square foot and operating efficiency, robust electrical protection, intelligent paralleling that optimizes performance and Dynamic Grid Support for enhanced grid interactive capabilities
- VRLA batteries in open battery stands or lithium-ion batteries in racks, providing battery back-up
- Floor mounted Vertiv<sup>™</sup> Liebert<sup>®</sup> PDX PI Air Conditioning and preinstalled condensers
- Thermal containment to isolate hot zone and cold zone airflows for optimum thermal performance
- Automatic Transfer Switch (ATS) functionality to reliably select normal or emergency power sources
- Overhead infrastructure, including piping, electrical distribution, and fiber ducts
- Clean agent fire suppression and aspiration smoke detection (as optional items)

#### Components overview of Vertiv<sup>™</sup> SmartMod<sup>™</sup> Combo



Enclosure Cut-Out view of Vertiv™ SmartMod™Combo

#### Vertiv<sup>™</sup> SmartMod<sup>™</sup> Max (White Space) unit:

- Classic and cost-effective
   Vertiv<sup>™</sup> racks
- Vertiv™ rack PDU's
- In-row Liebert thermal management units with intelligent controls - direct expansion cooling and chilled watter cooling options are available
- Thermal containment to isolate hot aisle and cold aisle airflows for optimum thermal performance
- Overhead infrastructure, including piping, electrical distribution, and fiber ducts
- Clean agent fire suppression and aspiration smoke detection (as optional items)

Based on preferred cooling option, SmartMod Combo is available with both direct expansion cooling units or chilled water based cooling units.

#### Vertiv<sup>™</sup> SmartMod<sup>™</sup> Combo Building Blocks



Power Modules (kVA)





#### Predefined Vertiv<sup>™</sup> SmartMod<sup>™</sup> Combo Configurations



### Vertiv<sup>™</sup> SmartMod<sup>™</sup> Combo Specifications

Vertiv"SmartMod" Combo configuration	PMSMM04021-182-000	PMSMM04021-113-000	PMSMM06021-124-000	PMSMM06021-183-000
			_	
	5	4	4	5
Layout				600
Vertiv <sup>™</sup> Power Module	180 - 180			
No of Power Modules			1	
External Dimensions per Module				
Enclosure Length (m)	11970	11970	13800	13800
Enclosure Width (m)		34	.00	
Enclosure Height (m)		35	00	
Overall Lenght (mm)	14400	14400	16200	16200
Weight (kg)	32000	32000	37000	37000
Input AC Parameters				
Region		EMEA	/ NAM	
Voltage/Frequency		400VAC/50Hz 0	or 480VAC/60Hz	
Electrical				
Power module topology		2	N	
Electrical Distribution Board		:	2	
Automatic Transfer Switch		:	2	
UPS Model		EX	L S1	
UPS Cabinet			2	
UPS Module Redundancy		I	N	
UPS Rating	400 kVA	400 kVA	600 kVA	600 kVA
Battery Backup Time	9 min BOL @360 kW	10 min BOL @330 kW	8 min BOL @500 kW	6 min BOL @540 kW
Mechanical (HVAC)				
Air Conditioning Type		Floor Mounted	Air Conditioning	
Air Conditioning Redundancy		N pe	r side	
Air Conditioning Units		Liebert® PDX PI041 +	HCR059 condensers	
Cooling Capacity for IT Load @35°C (kW)		40	0.6	
Exterior Ambient Operating Range		-30°C t	o +52°C	
Vertiv <sup>™</sup> SmartMod <sup>™</sup> Max				
No of SmartMod Max Modules	2	3	4	3
External Dimensions per Module				
Enclosure Length (mm)		119	970	
Single Enclosure Width (mm)		29	00	
Total Enclosure Width (mm)		58	310	
Enclosure Height (mm)		33	00	
Overall Length (mm)	17500	15400	15400	17500
Weight (kg)	2 x 15700	2 x 15200	2 x 15200	2 x 15700
IT Racks				
No of Racks	52	78	104	78
Rack Height (U)	42	42	42	42
Rack Depth (mm)	1100	1100	1100	1100
Rack Width (mm)	600	600	600	600
Rack Load (N)		80	00	
Electrical				
Rack Load (kW)	6.9	4.2	4.8	6.9
Busbar System			r row	
PDU	2 per rack			
PDU nominal Capacity	3x16A @ 230/400V-3ph or 30A/60A @ 120/208V			
PDU Type		Monitored	(unit level)	
Mechanical (HVAC)				
Air Conditioning Type		Air Cooled In-Row	Based Cooling Unit	
Air Conditioning Redundancy	N+1 per row			
Air Conditioning Units	Liebert® CF	RV CRD25 + CCD25 Condenser	or Liebert® CRV 035 + MCL055	Condenser
Cooling Capacity for IT Load @35°C (kW)	360	330	480	540
Exterior Ambient Operating Range		-30°C t	o +52°C	



## Vertiv<sup>™</sup> SmartMod<sup>™</sup> Combo 300 kW

CASE STUDY



### 300 kW

IT Load

### **Customer Need**

- The customer was new to the data centre colocation business and required a solution that allowed modular growth as they developed their market
- The initial design was based on traditional build methodology but required significantly more space with a large dependency on local build activities
- This approach introduced additional time and risk that the client wanted to mitigate

### Solution

- Based on Vertiv<sup>™</sup> SmartMod<sup>™</sup> Combo solution with 2 x SmartMod Max and 1 x Vertiv<sup>™</sup> Power Module 400 2N
- Phased deployment with 52 racks in Phase 1 and 52 racks in Phase 2
- Total IT load of 3 kW per rack, 156 kW total for phase 1
- In-row DX based cooling with N+1 redundancy per row
- 2N electrical architecture, 2 x EXL S1 200 kVA UPS with 10 min @312kW VRLA backup per side
- ACC, CCTV, Fire system within each room

- Optimized Power Module footprint
- Significantly reduced lead time to deliver data centre to site
- Client selling space for future deployments before the first phase was delivered

## 0.5 MW and more Vertiv<sup>™</sup> MegaMod<sup>™</sup>

Vertiv<sup>™</sup> MegaMod<sup>™</sup> Provides a High-Quality Prefabricated Modular Data Center Solution that can be deployed in expandable units of 0.5 or 1 MW for IT Loads up to 2 MW or more. Choose between the MegaMod and MegaMod Plus solution, that offers additional racks and cooling capacity with a dedicated IT and Cooling Modules.

#### Vertiv<sup>™</sup> MegaMod<sup>™</sup> Makes IT Easy to Deploy New Capacity at Speed

MegaMod<sup>™</sup> provides everything you need to get started with a fully equipped modular data center, from external power rooms, to cooling, racks, monitoring and fire protection. In addition, Vertiv also can provide end-to-end services for a worry-free startup and ongoing operations, including deployment, commissioning, ongoing maintenance, spare parts, and ongoing training.

#### MegaMod includes:

- UPS power protection Rely on the monolithic, transformer- free Vertiv™Liebert® EXL S1 UPS, which provides leading power per square foot and operating efficiency, robust electrical protection, intelligent paralleling that optimizes performance and Dynamic Grid Support for enhanced grid interactive capabilities.
- Batteries Gain reliable battery backup with Valve-regulated lead acid (VRLA batteries), or choose lithiumion as an upgrade, to gain longer lifespans, better performance in rugged conditions, and a lower total cost of ownership.
- Floor-mounted Vertiv™Liebert® PDX Air Conditioning – Benefit from cooling that provides the industry's highest efficiency, protection, and capacity per footprint for smaller space. Other cooling type options on request.
- Thermal containment Isolate hot containment, ensure aisle and cold containment, and maintain aisle airflows for optimum thermal performance.
- Classic and cost-effective Vertiv<sup>™</sup> racks – Store all equipment securely and efficiently, while easily accessing equipment for servicing.
- Vertiv<sup>™</sup> rack power distribution units (rPDUs) – Ensure reliable power distribution, with monitored and switched rPDUs.





Various building block layouts for Vertiv™ MegaMod™

- Automatic Transfer switching functionality – Easily navigate outages with automatic switching to secondary power sources.
- Overhead infrastructure Contains suspended piping, electrical distribution, and fiber ducts, away from electronics.
- Clean agent fire suppression and aspiration smoke detection –
   Protect your assets in the event of

Enclosure Cut-Out view of Vertiv™ MegaMod™



Various building block layouts for Vertiv™ MegaMod™ Plus

a fire with fast-acting detection and suppression systems.

 SCADA-based Building Monitoring System (BMS) with a SQL

**database** – Teams can use the BMS for real-time onsite or remote monitoring and visualization of critical infrastructure, with graphics, alarms, trending, user management, and database recording of sessions, keeping system performance high.





### Vertiv<sup>™</sup> MegaMod<sup>™</sup> Specifications

#### MegaMod<sup>™</sup> Platform Design Feasibilities

#### MegaMod<sup>™</sup> Reference Designs

		MegaMod <sup>™</sup> 0.5 MW	MegaMod <sup>™</sup> Plus 0.5 MW	MegaMod <sup>™</sup> 1 MW	MegaMod <sup>™</sup> Plus 1 MW
Comorol					
General					
Voltage/Frequency	400VAC, 50Hz		400VAC		
Ambient Operating Range	-30°C to +52°C		-30°C to	+40°C	
External Dimensions	( ) = (1)				
Enclosure Height (m)	4 / 5 <sup>(1)</sup>		4	F	
Enclosure Length (m)	Depending on final layout	14	26. 15.5	24	31
Enclosure Width (m) Stackability	Depending on final layout Yes, as option	14	Not featured in Re		31
			Not leatured in No	sierence Design	
IT Hall					
IT Racks					
No. Of Racks : Width - 600 mm	up to 128 per 0.5 MW IT Hall block	96	120	192	240
No. Of Racks : Width - 800 mm	up to 96 per 0.5 MW IT Hall block		Not featured in Re	eference Design	
Rack Height	42U / 47U / 48U		420	J	
Rack Depth	1100 mm / 1200 mm		1100	mm	
Rack Load	8 kN		8 k	N	
Electrical					
Max IT Load (2)	up to 2 MW	500 kW	500 kW	1000 kW	1000 kW
Average Rack Density	4 - 8 kW	5.2 kW	4.4 kW	5.2 kW	4.4 kW
Busbar System	A+B side		A+B s	side	
PDU	Two per rack		Two pe	r rack	
PDU Capacity (max)	3x16A @ 230 / 400V - 3 phase		3x16A @ 230 / 4		
	Basic, Monitored (unit level)		0,10,7 @ 200 / 4		
PDU Type	or Switched (unit level)		Monitored (	unit level)	
Mechanical (HVAC)					
Air Conditioning Type	Perimeter cooling, direct expansion	Perimeter cooling, direct expansion			
Air Conditioning Redundancy	N+1	N+1			
Air Conditioning Units	Liebert PDX PI/PX82-120 + HCR59 - 99 or MCM/L 55-100 with Econophase	Liebert PDX PI120 + HCR88 condensers (2 condensers per unit)			
Ventilation type	Roof mounted Air Handling Unit, with humidifier, DX dehumidification	Roof mounted Air Handling Unit, 1000 m3/h, with humidifier, DX dehumidification		er,	
Power Module					
Electrical					
Power module topology	N / 2N	2N within	single module	N within sinale ma	odule / two modules
Main Switch Board w/ UPS Bypass	Depending on final Power Module specification	3p1600A, TP8	&N+E, 400V/50HZ ec FORM 4 Type 2; IP 31	3p3200A, TP&I	N+E, 400V/50HZ CFORM 4 Type 2; IP 31
Automatic Transfer Switch	Breaker Based		Breaker	9	, po _,
UPS Model	EXL S1		EXL		
UPS Rating	600 / 1000 / 1200 kVA	60	D0 kVA		) kVA
Battery Backup Time	+5 min				
, .		5 min @ 500 kW EOL 5 min @ 1000 kW EOL			
Battery Type	VRLA / Li-ion (optional)		VRL	.A	
Mechanical (HVAC)					
Air Conditioning Type	Perimeter cooling, direct expansion		Perimeter cooling,	direct expansion	
Air Conditioning Redundancy	Ν		Ν		
Air Conditioning Units	Liebert PDX	Liebert PDX	( PI041 + HCR59	2 x Liebert PD	( PI041 + HCR59

 $^{(1)}$  Actual module height may vary due to roof mounted condensers. 5m height includes roof support beam installed on site.

 $^{(2)}$  Maximum IT load at dT=15°C for MegaMod and dT= 12°C for MegaMod Plus.

## Vertiv<sup>™</sup> MegaMod<sup>™</sup> 1.1 MW

#### CASE STUDY



### 1.1 MW

IT Load

### **Customer Need**

• 1.1 MW IT Load, rapid schedule, easy shipping and site construction, Tier III certificate,

#### Solution

- The integrated data center solution delivered by Vertiv contained:
  - Modular, hot/cold aisle configuration, and power, IT, and battery modules
  - 156 DCM racks; 2 x PDU per each rack
  - PCW cooling units with Vertiv<sup>™</sup> SmartAisle<sup>™</sup> technology
  - 4 x 500KVA N+1 UPS configuration
  - Busbar distribution power system and high energy efficiency
  - Tier III compliant power and cooling architecture

#### Result

• Delivered project and met customers expectations on quality and requested reliability



## Vertiv<sup>™</sup> MegaMod<sup>™</sup> 1.1 MW

#### CASE STUDY



### 1.1 MW

IT Load -

#### **Customer Need**

- Looking to rapidly expand their available colocation white space
- Highly reliable, world-class facility offering future flexibility and enhanced performance

#### Solution

- Prefabricated modular data center consisting of 120 racks with expansion to up to 286 racks, and including Vertiv power and thermal management technologies, as well as advanced Lithium Ion batteries for reduced operational expenses
- Solution was prefabricated, integrated and tested in Vertiv facility, then disassembled into 12 shippable units and packed for transport

- Solution was shipped, reassembled on-site and ready for testing in under 6 weeks
- Reliable, low-risk partner ensuring projects remain on-time and on-budget
- Ongoing local support for operations

## 0.5 MW and more Vertiv<sup>™</sup> SmartMod<sup>™</sup> HDX

Latest developments in AI, IoT, cryptocurrencies, AR/VR reality and the exponential growth in data, means that today businesses need access to computers capable of performing complex workloads. This in turn has resulted in a need for data centers where a single IT rack can support densities of 20 kW and higher.

For such applications, where air-cooling can cover the increased heat loads, Vertiv has developed a standardized prefabricated data center offering - the Vertiv<sup>™</sup> SmartMod<sup>™</sup> HDX.

This simple, scalable data center design uses pre-engineered Vertiv<sup>™</sup> building blocks to create a full solution – the Power Module, IT Hall and Chiller Skid. This next generation High Power Density data center utilizes the Vertiv<sup>™</sup> Liebert<sup>®</sup> DCL or active Vertiv<sup>™</sup> Liebert<sup>®</sup> DCD cooling solutions to support rack density up to 50 kW/rack.

Based on preferred cooling option, SmartMod Combo is available with both direct expansion cooling units or chilled water based cooling units.

To showcase the capabilities of this high power density datacenter platform, take a closer look at our two Vertiv<sup>™</sup> SmartMod<sup>™</sup> HDX Reference Designs

- Vertiv<sup>™</sup> SmartMod<sup>™</sup> HDX DCL
   DCL cooling-based solution
- Vertiv<sup>™</sup> SmartMod<sup>™</sup> HDX DCD - DCD cooling-based solution

The SmartMod<sup>™</sup> HDX solution can further adapt to your specific rack quantity and rack density.

# SmartMod HDX data center solution includes:

- **UPS power** –Monolithic Vertiv<sup>™</sup> Liebert<sup>®</sup> EXL S1 UPS, with Dynamic Grid Support for enhanced grid interactive capabilities
- **Batteries** Reliable battery backup with Valve-regulated lead acid (VRLA), or lithium-ion batteries
- Liebert<sup>®</sup> DCL Modular Rack Cooling, Closed Loop Cooling Architecture (up to 35 kW/rack)

or

 Liebert<sup>®</sup> DCD rear-door heat exchangers

(passive or active, up to 50 kW/rack)

 Vertiv<sup>™</sup> Liebert<sup>®</sup> HPC-S chillers with free-cooling option



Cut off view of the Vertiv™ SmartMod™ HDX DCL

- Vertiv<sup>™</sup> racks
- Vertiv<sup>™</sup> rack power distribution units (rPDUs)
- Automatic Transfer switching functionality – Automatic switching between primary and secondary power sources.
- Overhead infrastructure -Including chilled water piping, fiber ducts and mesh cable trays
- Clean agent fire suppression and aspiration smoke detection (as optional item)
- Ancillary systems CCTV, Access Control and Intrusion Detection (as

optional items)

 SCADA-based Building Monitoring System (BMS) with a SQL database (as optional item)



Cut off view of the Vertiv™ SmartMod™ HDX DCD



## Vertiv<sup>™</sup> SmartMod<sup>™</sup> HDX Design Specifications

	SmartMod™ HDX DCD	SmartMod™ HDX DCL		
General				
Voltage/Frequency	400VAC	; 50Hz		
Ambient Operating Range <sup>(1)</sup>	-25°C to +45°C <sup>(1)</sup>	-25 °C to +43°C <sup>(1)</sup>		
IT Hall				
IT Racks				
No. Of Racks: Width - 600 mm	-	11		
No. Of Racks: Width - 800 mm	26	-		
Rack Height	420	U		
Rack Depth	1200	mm		
Rack Load	12 k	N		
Electrical				
Max IT Load	600 kW	385 kW		
Rack Density	up to 50 kW	up to 35 kW		
Busbar System	A+B s	side		
PDU	Тwo ре	r rack		
PDU Capacity (max)	3x63A @ 230/4	3x63A @ 230/400V - 3phase		
PDU Type	Basic, Monitored (unit leve	I) or Switched (unit level)		
Mechanical (HVAC)				
Cooling Technology	Air-water heat exchanger mounted on rack cabinets rear-door	Air-water cooling unit for lateral attachment to server cabinets		
Cooling Redundancy	N+	1		
Cooling Units	Vertiv™ Liebert® DCD Active + Vertiv™ Liebert® HPC-S Freecooling Chiller	Vertiv™ Liebert® DCL Hybrid + Vertiv™ Liebert® HPC-S Freecooling Chiller		
Power Module				
Electrical				
Power module topology	N or	2N		
Main Distribution Board section	400V, 50Hz, Form 4 Typ	be 2, IP31, 36kA @ 1sec		
Automatic Transfer Switch	Breaker	Breaker Based		
UPS Model	Monolithic c	Monolithic or Modular		
UPS Rating	up to 800 kVA	up to 500 kVA		
Battery Backup Time	up to 10	up to 10 min		
Battery Type	VRLA / Li-ior	VRLA / Li-ion (optional)		
Mechanical (HVAC)				
Cooling Technology	Chilled Water Floor-M	Chilled Water Floor-Mounted Cooling Unit		
Cooling Redundancy	Ν			
Cooling Units	PCW			

(1) Maximum altitude 500 m and maximum glycole content 45%. Operating Temperature Range can be extended to reach down to -30 or up to +52 °C

## 0.5 MW and more

## Vertiv<sup>™</sup> Custom

In addition to its standardized offerings, Vertiv also designs, manufactures and deploys Custom data centers. Here, we are able to build, in close cooperation with the customer, a full prefabricated Data center according to their specific requirements.

Typically, these data centers are for deployments of IT loads up to 20 MW or more.





## Hyperscale Cloud Colocation

#### CASE STUDY



#### 4.9 MW

IT Load

#### **Customer Need**

- 4.9 MW of computing power within 14 months
- Hyperscale cloud tenant-specific requirements and limited site footprint two-story deployment

### Solution

 Dividing computing infrastructure among two locations — a 900-kilowatt (kW) expansion within existing M-VAULT and a greenfield site, which is the newest M-VAULT hosted at QSTP and designed for 8 MW

- Vertiv<sup>™</sup> Liebert<sup>®</sup> EXL S1 UPS provided MEEZA up to 99% energy efficiency in Dynamic Online mode. With its intelligent paralleling feature, the UPS can even optimise efficiency at partial loads, which achieves cost savings by minimising energy losses.
- Largest PFM data center campus in MEA region
- 14 months turnkey schedule with Local Partner delivering the turnkey works

# Hybrid Data Center Design

## What is hybrid?

The hybrid modular data center approach incorporates off-site prefabrication of complex building blocks (power modules/skids, cooling and hydro modules/skids, and whitespace superstructure) into or next to traditionally constructed buildings with seamless on-site integration to speed up the fitting out of a traditional build or existing data center.

These are scalable, flexible designs for larger deployments up to 40 MW IT, with 450 to 1500 racks. Deployment time on hybrid modular solutions is usually 9 to 16 months, depending on complexity, with a possibility of inventory stock for rapid rollout of expansion.





Here you can read more about

► HYBRID MODULAR DATA CENTER WHITE PAPER



# Vertiv<sup>™</sup> Power Module & Skid

Vertiv<sup>™</sup> Power Module is critical power infrastructure in prefabricated, easily expandable modular blocks primarily for data center applications allowing customer and designer to focus on the sensitive areas of the facility that require the most attention and management.

Power Module sizes are typically up to 2500+ kVA and they leverage core Vertiv<sup>™</sup> Critical Power and Thermal Management technologies to deliver a simple, yet robust design that grows with data center needs at the most critical locations.



All subsystems are factory installed into a secure, weatherproof, and transportable enclosure. The enclosure simplifies and drastically shortens the on-site time required to install and startup, and reduces the potential for risk, quality, or schedule delays. The entire Vertiv Power Module and its sub-systems are designed to minimize additional work required at the site – from arrival on site to startup and commissioning in days instead of months.

#### Vertiv<sup>™</sup> Power Module incorporates:

- Vertiv<sup>™</sup> Liebert<sup>®</sup> UPS offers industry leading power density and proven reliability
- Multiple switchboard configurations offer distribution options for both critical (UPS-protected) and non-critical downstream loads
- Flexible incoming and outgoing power connections, wall or floor, that can match the needed site architecture
- Breaker-based normal to emergency power automated transfer
- Integral energy storage with VRLA or Li-ion batteries
- Redundant Vertiv<sup>™</sup> Liebert<sup>®</sup> Thermal Management units with air containment – ensuring optimal operating conditions for all subsystems, even in the event of utility power loss
- Clean agent fire suppression to reliably protect assets in the event of a fire
- SCADA-based Building Monitoring System (BMS) with a SQL database

   Teams can use the BMS for real-time onsite or remote monitoring
   and visualization of critical infrastructure, with graphics, alarms,
   trending, user management, and database recording of sessions,
   keeping system performance high

#### Highlights

- High power density built around market-leading Vertiv<sup>™</sup> Liebert<sup>©</sup> UPS technology
- Energy efficient operation with airflow containment to ensure optimal equipment conditions
- Rapid deployment with limited site work enabling nearly "plug and play" functionality
- Simple, hot scalability of your site's power capacity by simply adding more Vertiv<sup>™</sup> Power Modules
- System efficiency up to 95%

#### Example topologies: 0 6 N+1 3MV -- 11110 Single module represents a N redundant system 1 x UPS - 1000/1200kVA Max Battery runtime: 5min @1000kW EOL Individual Transformer & Generator inputs UPS and Mechanical/Non-Critical load outputs 2N CUSTOMER FACILITY 1MW -- |||| Maximized floor space for revenue generating equipment. Multi module configuration allows for various site power topologies based on customer requirements (2N, N+1) Scalability - Modules can be added based on initial power requiremets a future expansion plans.

## Capacity & Installation Flexibility



## Vertiv<sup>™</sup> Power Module Technical Specifications

	Power Module		
Enclosure External Dimensions			
Enclosure Length	Up to 17m 52'		
Enclosure Width	Up to 4m	12'	
Enclosure Height	Up to 4m	12'	
Estimated Transportation Weight	Up	to 45t	
Enclosure Type	Steel Fra	me and Walls	
Electrical			
Region	EMEA	NAM	
Voltage / Frequency	230/400V-3ph / 50Hz	480-3ph / 60Hz	
Recommended Transformer Size	Up to	3150 kVA	
UPS Type	Liebert® EX	′L S1, Trinergy™	
UPS Rating	up to	2500 kVA	
Main Switch Board Rating	up te	5000A	
Rated Short-Time Withstand Current (Icw@1s)	up to 100	kAIC @ 600V	
Form of Separation	up to Fo	orm Type 4b	
Automatic Transfer Switch	Open/Clos	sed Transition	
Load Bank	Prepared with Camlock Connections		
Battery			
Battery Type	VRLA or Li-ion		
Estimated Battery Backup	5 min @ Full Load, EOL		
Cooling			
Cooling Type	Air cooling; Direct Expans	ion with Optional Free Cooling	
Cooling Unit Model	Lieb	ert® PDX	
Cooling Unit Redundancy	Ν	or N+1	
Exterior Ambient Operating Range	-20°C to +50°C -35°C to 40°C		
Fire Detection and Suppression			
Fire Detection System	Smoke/Heat detection Conventional		
Fire Suppresion System	FK 5-1-12 HFC-227A (FM-200)		
Very Early Smoke Detection System	Optional		
Monitoring			
EPMS	HMI with PLC; Single Customer Interface Based on OPC UA/MQTT Protocol		
Optional	Video Surrveilance, Access Control, Intrusion Detection		



Here you can learn more about

► VERTIV POWER MODULES

## Vertiv<sup>™</sup> Power Module 1.2 MW

#### CASE STUDY



#### 1.2 MW Power Output

#### **Customer Need**

- Our Key Account needed 1.2 MW prefabricated power rooms for the next phases of their Large Colocation Datacenter in Ireland
- We managed to secure business by leveraging on our experience on Power modules and optimizing solution footprint while meeting project requirement

### Solution

- Vertiv worked with the client to develop a 1.2 MW Power module that is fully compliant to local regulations, meets project requirements and supports project delivery dates
- Full BIM Model developed, integrating into the overall site BIM
- Delivered solution fully meeting client performance and resiliency requirements

- Delivered, deployed and commissioned 12 x 1.2 MW Power modules, successfully meeting project schedule and performance requirements
- Delivered solution successfully met and passed stringent end client commissioning



## Vertiv<sup>™</sup> Power Module 1.2 MW

CASE STUDY



#### 1.2 MW

**Power Output** 

#### **Customer Need**

- Large Colocation Datacenter constructed using modular power rooms to speed up delivery and optimize cost
- Meet client specific requirements and create a resilient power architecture by using 1,2MW prefabricated power rooms
- Utilize New Li-Ion battery technology to optimize footprint

### Solution

- Power Module with 1200kW UPS
- Li-Ion batteries for 5min battery backup
- Roof top mounted condenser units
- N+1 redundancy on air-conditioning system Designed in accordance with local regulations
  - All material used certified as per EAC

- Delivered, deployed and commissioned 8 x 1.2 MW Power modules, successfuly meeting project • schedule and performance requirements
- Delivered solution successfuly met and passed stringent end client commissioning •

## Hyperscale Data Center Power Skid

#### CASE STUDY



## 1.6 MW

#### **Power Output**

#### **Customer Need**

- Power Skidded Electrical Rooms
- Large Scale capacity/throughput production
- Expertise in Electrical Integration

#### Solution

- 1.6 MW Power Output Skidded Electrical Rooms
- 150+ skids delivered to over 10 program sites
- Integrated Equipment includes:
  - 156 DCM racks; 2 x PDU per each rack
  - PCW cooling units with Vertiv<sup>™</sup> SmartAisle<sup>™</sup> technology
  - 4 x 500KVA N+1 UPS configuration
  - Busbar distribution power system and high energy efficiency
  - Tier III compliant power and cooling architecture

- Solution was held in factory for extra weeks for early completion
- Satisfied customer and delivery
- Growing pipeline with client



## Vertiv<sup>™</sup> Power Module 1.7 MW

#### CASE STUDY



#### 1.7 MW

#### Power Output

#### **Customer Need**

- Large Colocation Datacenter in Amsterdam constructed using modular power rooms to speed up delivery and optimize cost
- Meet client specific requirements and create a resilient power architecture by using 1.7 MW prefabricated power rooms

### Solution

- Vertiv worked with the client to develop a 1.7 MW Power module (2 MW UPS capacity) that meets project requirements and supports project delivery dates
- Full BIM Model developed, integrating into the overall site BIM
- Delivered solution fully meeting client performance and resiliency requirements

- Delivered, deployed and commissioned 34 x 1.7 MW Power modules, successfully meeting project schedule and performance requirements
- Delivered solution successfully met and passed stringent end client commissioning

# Vertiv<sup>™</sup> Unit IT

Vertiv<sup>™</sup> Unit IT is a prefabricated infrastructure intended for data center white space. It consists of air containment, busbars and tap-off boxes, cable trays, fiber runners, lights and, optionally, fire detection and suppression. Vertiv Unit IT is installed over the IT racks, either self-supported or suspended.

Vertiv Unit IT simplifies designing IT space with Vertiv configured infrastructure blocks. The unit is fully prefabricated and tested in Vertiv integration facility. Subsequent installation on site takes hours compared to days with traditional white space furnishing.

The configuration of the Vertiv Unit IT itself is configurable, with dimensions depending on various Whitespace site specific design requirements.





# Vertiv<sup>™</sup> HydroMod<sup>™</sup>

Vertiv<sup>™</sup> HydroMod<sup>™</sup> prefabricated cooling systems can offer a convenient and cost-effective solution for data center cooling applications. Prefabricated cooling system is a modular unit that is designed, built, and tested off-site, and then delivered and installed on-site with minimal disruption.

Vertiv provides a variety of HydroMod solutions:

#### 1. Prefabricated Water Treatment System

- System sizing data centers from 0.5 to 2.5 MW IT load
- Support for adiabatic and evaporative cooling systems
- Scalable depending on site water quality
- Skidded single-transport solution

#### 2. Prefabricated Chilled Water System

- System sizing data centers from 0.5 to 2.5 MW IT load
- Support for primary and secondary cooling systems
- Scalable depending on site sizing requirements
- Skidded single-transport solution
- Requires only connection to CHW system and power supply
- Can be connected in parallel to achieve redundancy





# When Innovation meets Sustainabilty

# Vertiv<sup>™</sup> TimberMod<sup>™</sup>

Data center owners and operators want to improve their ability to meet evolving sustainability requirements. One approach is to reduce the embodied carbon of the new capacity they deploy.

Embodied carbon includes non-operational emissions, including the extraction, manufacturing, transportation, and installation of materials and components used to build and deploy new facilities.<sup>1</sup> Data centers are typically constructed of concrete (up to 40%), fuel (around 25%), and steel (around 10%).<sup>2</sup> Across industries, steel contributes 10% of global carbon emissions, while concrete contributes 6% to 11%.<sup>3</sup>

Data center owners and operators can reduce embodied carbon by choosing different materials and manufacturing methods to deploy new capacity. Mass timber can be considered a more environmentally sustainable building material than concrete or steel because it can be renewable if harvested using sustainable processes. Mass timber also stores carbon captured from the environment.<sup>4</sup> As a result, "mass timber construction can function as a form of carbon removal when combined with sustainable timber production and building demolition practices."<sup>5</sup>

Vertiv prefabricated modular data centers (PFM) offer new IT and power capacity in modular building blocks, supporting business growth while avoiding carbon emissions due to unused capacity. Now, data center owners and operators have fresh options with Vertiv<sup>™</sup> TimberMod<sup>™</sup>, a PFM structure made of mass timber that can be applied to **Vertiv<sup>™</sup> Power Module** and **Vertiv<sup>™</sup> SmartMod<sup>™</sup>** infrastructure.



<sup>&</sup>lt;sup>1</sup> Joseph Hawkins, "The embodied carbon challenge for truly net-zero data centers," article, DatacenterDynamics, September 21, 2023, <u>https://www.datacenterdynamics.com/en/marketwatch/the-embodied-carbon-challenge-for-truly-net-zero-data-centers/</u>

<sup>2</sup> Dan Swinhoe, "Sustainable data centers require sustainable construction," article, DatacenterDynamics, article, May 12, 2021, <u>https://www.datacenterdynamics.com/en/analysis/sustainable-data-centers-require-sustainable-construction/#</u> <sup>3</sup> Gideon Fink Shapiro, "Concrete, Steel, or Wood: Searching for Zero-Net-Carbon Structural Materials," Architect Magazine, January 15, 2020, <u>https://www.architectmagazine.com/technology/concrete-steel-or-wood-search-inc-for-zero-net-carbon-structural-materials\_o</u>

<sup>4</sup> "What Is Mass Timber Construction," fact sheet, American University, updated June 24, 2020, <u>https://www.american.edu/sis/centers/carbon-removal/fact-sheet-mass-timber.cfm#</u>. <sup>5</sup> Ibid



#### Solutions with Vertiv<sup>™</sup> TimberMod<sup>™</sup> structure

#### Vertiv<sup>™</sup> SmartMod<sup>™</sup>



Vertiv™ Power Module



SmartMod<sup>™</sup> is an all-in-one modular data center featuring all equipment necessary for normal data center functionality. All subsystems are factory installed into a secure, weatherproof and transportable enclosure – simplifying and shortening the on-site time required to install and startup.

With Vertiv<sup>™</sup> Power Module you can rapidly construct redundant blocks of critical power infrastructure for your new or existing facility, allowing you to focus on the sensitive areas of the facility that require the most attention and management.

#### Deploy Vertiv<sup>™</sup> TimberMod<sup>™</sup> to Accomplish Key Business Goals

With TimberMod, data center owners and operators gain a solution that meets their business, technical, operational, and sustainability objectives.

Deployable in modular building blocks of IT and power capacity, TimberMod has an appealing architectural design that transcends data center applications and blends into any environment. Vertiv provides end-to-end services to ensure a straightforward startup and smooth ongoing operations. These services include deployment, commissioning, ongoing maintenance, remote monitoring, and training. Use TimberMod to meet business and performance objectives while reducing carbon emissions.



\* Calculations were performed using One click LCA software and Level(s) framework, both compliant with EU taxonomy-Calculation method (EN 15978:2011). Sources for the material Environmental Product Declaration (EPD) are taken for the design phase. Data used in calculations comes from equivalent design phases of two Vertiv<sup>™</sup> Power Modules. The calculation was carried out for the cradle (A1) to gate A3 and the transport of materials and structure elements to the assembly site (A4) - in this case our factory site in Rugvica, Croatia. The equipment was excluded from the calculation since it represents the common denominator for both buildings.



#### Here you can read more about

► VERTIV TIMBERMOD

#### Accomplish More Sustainability Goals with Vertiv™ TimberMod™

Vertiv TimberMod addresses data center owners' and operators' desires to use more sustainable processes – without compromising performance or speed to market TimberMod™:

 Leverages mass timber as a structural element: Built with mass timber, TimberMod offers the same level of reliability as steel, ensuring robust performance when encountering seismic activity, wind forces, and structural demands.

Uses natural materials: Mass timber can be a renewable construction material based on how it is produced, harvested, and used. Organizations that deploy TimberMod can minimize resource depletion and reduce carbon dioxide emissions.

The European Commission is developing a roadmap to reduce the whole-life carbon of the building sector by 2050 by focusing on operational and embodied emissions. This regulation could spur data center owners to adopt mass timber as a construction material for new capacity in the European Union.<sup>6</sup>

## • Can be flexibly and rapidly deployed:

Offering prefabricated critical power and IT infrastructure, TimberMod is ideal for small and medium-sized data centers that want to deploy new capacity at pace.

<sup>6</sup> "MEPs back plans for a climate neutral building sector by 2050" press release, European Parliament, March 14, 2023, https://www.europarl.europaeu/eur



Vertiv.com | Vertiv Headquarters, 505 N Cleveland Ave, Westerville, OH 43082, USA

© 2024 Vertiv Group Corp. All rights reserved. Vertiv<sup>™</sup> and the Vertiv logo are trademarks or registered trademarks of Vertiv Group Corp. All other names and logos referred to are trade names, trademarks or registered trademarks of their respective owners. While every precaution has been taken to ensure accuracy and completeness here, Vertiv Group Corp. assumes no responsibility, and disclaims all liability, for damages resulting from use of this information or for any errors or omissions. Specifications, rebates and other promotional offers are subject to change at Vertiv's sole discretion upon notice.