

LIEBERT® NXL™ 500-750kVA, 1+N (DISTRIBUTED BYPASS) MULTI-MODULE SYSTEM SITE PLANNING DATA

Table 1 Site planning data—500-750kVA

| UPS Rating | | AC Input/ Output Voltage, VAC | Input Isolation Transformer | Rectifier AC Input Current | | Bypass/ Output AC Current | Maximum Battery Current at End of Discharge (A) | Maximum Heat Dissipation, Full Load, BTU/h (kW) | Dimensions WxDxH, in. (mm) | Approximate Weight Unpacked, lb. (kg) |
|------------------|-------|-------------------------------------|-----------------------------------|-------------------------------|------|------------------------------|--|--|---|---|
| kV A | kW | | | Nom | Max | Nom | | | | |
| 500 | 450 | 480 | YES | 643 | 804 | 601 | 1250 | 124,805 (36.6) | 111.6x39.4x76.8 (2835x1000x195 0) | 10,410 (4722) |
| 625 | 562.5 | 480 | | 799 | 995 | 752 | 1530 | 167,265 (49.0) | 140.5x39.4x76.8 (3568x1000x195 0) | 13,800 (6260) |
| 750 | 675 | 480 | | 975 | 1219 | 902 | 1845 | 213,587 (62.6) | | |
| 750 | 675 | 575 | | 815 | 1018 | 753 | 1851 | 215,790 (63.2) | | |
| 750 | 675 | 600 | | 759 | 949 | 722 | 1851 | 200,173 (58.7) | | |
| See Notes below: | | | — | 1,3,6,7,8,10,11 | | 2,3,4,6,7,8,10,11,13 | 5,6,7,8,10,11 | — | 9, 12 | 9,12 |

Notes for Table 1

1. Nominal rectifier AC input current (considered continuous) is based on full rated output load. Maximum current includes nominal input current and maximum battery recharge current (considered non-continuous). Maximum input current is controlled by current limit setting which is adjustable 25 to 125% of nominal input current.
2. Bypass AC input and AC output current (considered continuous) is based on full rated output load.
3. Vertiv recommends that feeder protection (by others) for the rectifier AC input and the bypass AC input be provided by separate overcurrent protection devices.
4. UPS output load cables must be run in separate conduit from input cables.
5. Power cable from module DC bus to battery should be sized for a total maximum 2.0V line drop (power cable drop plus return cable drop as measured at the module) at maximum discharge current.
6. Grounding conductors to be sized per NEC 250-95. Neutral conductors to be sized for full capacity-per NEC 310-16, Note 10-for systems with 4-wire loads and 20% minimum capacity for 3-wire loads.
NOTE: A neutral conductor is required from each multi-module unit output to the system paralleling switch board.
7. Rectifier AC Input: 3-phase, 3-wire, plus ground
Bypass AC Input: 3-phase, 4-wire, plus ground (3-wire plus ground in certain circumstances)
AC Output to Load: 3-phase, 3- or 4-wire, plus ground
Module DC Input from Battery: 2-wire (positive and negative), plus ground
Module Output to SPC: 3-phase, 4-wire, plus ground
8. All wiring is to be in accordance with National and Local Electrical Codes.
9. Minimum overhead clearance is 2 ft. (0.6m) above the UPS.
10. Top or bottom cable entry through removable access plates. Cut plate to suit conduit size.
11. Control wiring and power cables must be run in separate conduits. Control wiring must be stranded tinned conductors.
12. Dimensions and weights do not include the System Paralleling Cabinet.
13. For optimal load sharing performance, the difference in bypass circuit cable length must be 10% or less from longest to shortest. Cable length should be measured from common point of input to common point of output. If needed, contact your Vertiv representative to determine if other lengths are acceptable.

